

SOMERVILLE  
MIDDLESEX COUNTY  
MASSACHUSETTS



FOR CONTINUATION  
SEE DWG C19BAT2P01

INNER BELT ROAD

HEX MANHOLE  
STA. 8+80  
Conc. 3.2'x4.5'x4'D  
C19BA-201

HEX (3)-4" PVC DUCTS  
(BUILT IN 2020)  
20 LF

JNF MANHOLE  
STA. 9+04  
Conc. 4'x4'x4'D  
C19E1-104

PROJECT INTERFACE  
C19BA/C19E1  
STA. 9+04

BURIED WITH MIN 24" OF COVER UNLESS  
OTHERWISE SPECIFIED  
AS-BUILT TWDX TRENCH  
C19E1 JOINT NETWORK FACILITIES (JNF)  
(BUILT IN 2019)  
393 LF-c/c

JNF (2)-4" PVC DUCTS

3RD AVENUE

CNS 4" PVC DUCT

AS-BUILT TWDX TRENCH  
(BUILT IN 2019)  
46 LF

ZAYO MANHOLE SOM8A

70 INNER BELT ROAD  
SOMERVILLE, MA

CoreSite ZERO MANHOLE

HEX (4)-4" PVC DUCTS

SEE SHEET 3  
DWG C19BAT1P03

HEX RUNNING LINE  
2' (TRENCH WIDTH)

BURIED WITH MIN 24" OF COVER UNLESS  
OTHERWISE SPECIFIED  
AS-BUILT TWDX TRENCH  
C19BA HUB EXPRESS SYSTEM (HEX)  
(BUILT IN 2020)  
538 LF-c/c

**NOTICE TO UTILITY LOCATORS:**  
All TOWARDEX owned underground facilities, including ducts and cable vaults shall be delineated and marked on surface with identifying abbreviation of "TWDX"



Y:\IP Planning\HubExpress (HEX) Program\As Built System Diagrams\C19BAT1P99.dwg  
Feb 09,2021 - 10:23pm by gkeyes

PREPARED BY:



PREPARED FOR:



PROJECT TITLE:

AS-BUILT CONDUIT PLACEMENT PLAN  
70 INNER BELT ROAD  
SOMERVILLE, MA 02143

SHEET NUMBER:

4

OF 4 SHEETS

Designed by J. CONNOR	Checked by J. KENNEDY	Date 2/3/2021	CONDUIT RECORD PLAN
--------------------------	--------------------------	------------------	---------------------

